



Status and planning of the CMX

Wojtek Fedorko for the MSU group
TDAQ Week, CERN
April 23 - 27, 2012




- Will replace CMM:
 - Backplane rate 40 → 160Mbps
 - Crate to system rate (LVDS) 40 → 160Mbps
 - Cluster information sent to Topological Processor (optical)
 - Optional partial TP functionality
 - **Standalone TP is now planned**
 - Some TP capability also designed onto the CMX


CMX: Use scenario with standalone TP



The CMX overview



CMX: modular design, most cards assembled without TP functionality




- Engineering @MSU
 - Philippe, Dan, and Chip
- CMX input module firmware @CERN
 - Wojtek and Yuri
- VME/ACE/TTC (VAT) interface @CERN
 - Yuri
- Request from Chris and David - to address and present:
"The detailed timeline & schedule from now until completion of commissioning at Point 1 in 2014 and a set of milestones associated to this schedule - typically ~10, including details of review procedure"
- Initial CMX development schedule is still valid
 - Minor adjustments

- 2011: Project and engineering specifications
 - CMX project Preliminary Design Review (Done)
 - Preliminary design studies
 - Test rig installed, checked out at MSU (postponed until 2012)
- 2012: Prototype design and fabrication
 - CMX schematics and PCB layout
 - Production Readiness Review
 - Prototype fabrication, CMM firmware ported on CMX
 - Basic tests for backward compatibility in test rig at MSU
- 2013: Prototype testing/installation/commissioning, final fabrication
 - Full prototype tests in test rig at CERN
 - CMX firmware development and test
 - Test in the L1Calo system during shutdown
 - Fabricate and assemble full set of CMX modules
- 2014: Final commissioning in the L1Calo trigger system in USA15


<https://indico.cern.ch/getFile.py/access?contribId=31&sessionId=6&resId=0&materialId=slides&confId=152943>

- 2012: Prototype design and fabrication
 - CMX schematics and PCB layout
 - CMX technology choice (FPGA choice, CMX/TP functionality) - DONE
 - 6U VME test card for VAT interface – PCB ready for testing in June
 - Real-time data path layout (ongoing)
 - CMX input module firmware currently under test on the XILINX development module
 - Power budget estimate
 - Prototype fabrication
 - mechanical testing in January
 - Will happen within ~month, not urgent yet.
 - Blank card, backplane connectors, front panel tests.
 - CMM firmware ported on CMX
 - Firmware for VAT interface (2 CPLD + TTC FPGA) to Spartan-3AN FPGA (Adapt VHDL code, create test bench, specify VME register model) (Yuri)
 - Most of the work completed at Stockholm (Pawel Plucinski, Sam Silverstein)
 - Needs to be adapted to final package choice
 - Basic tests for backward compatibility in test rig at MSU
 - Production Readiness Review (L1Calo/TDAQ) Fall/Winter
 - PRR after the prototype(s) is tested and
 - final check before going into full production

- Clock+Parity encoded on single line
- Variable duty cycle




• Setup:



- Scheme tested using Virtex 6 eval board
- Data capture developed, simulated and 'Placed and Routed' on target FPGA
 - Needs repeating – different package chosen




2012: PCB layout: VME/ACE/TTC (VAT) interface test card





VME/ACE/TTC (VAT) part of CMM

- Redesign HW with new components
 - Fit design into single device
- 6U VME test card for
 - Hardware implementation
 - Main FPGA re-configuration
 - Software
 - To be merged into CMX design
- PCB arrives in June
- Next:
 - Firmware for VAT card
 - Firmware for Virtex 6 FPGA
 - Test Stand and software



- Challenging milestone
 - Signal density
 - Avoid contention
- Drives FPGA package choice
- Implications for Firmware design



- 2013: Prototype testing/installation/commissioning, final fabrication
 - Full prototype tests in test rig at CERN
 - Test in the L1Calo system during shutdown
 - Fabricate and assemble full set of CMX modules

- Schedule proposed is maintained
 - Minor adjustments
- Tasks proceeding according to plan
- Need more detailed set of steps for in-situ tests before and after first beam
- Optimistic outlook for project completion