

CMX: installation, integration and commissioning plans

Chip Brock, Dan Edmunds, Philippe Laurens,
Savanna Shaw @MSU

Yuri Ermoline, **Duc Bao Ta** @CERN


Wojciech Fedorko @UBC

Pawel Plucinski @Stockholm University

3 December 2013



Overview



Three functional CMX prototypes expected end of December

Overview

I. Initial testing

- Initial board checkout @ MSU
- Board interface tests @ MSU/CERN
- *Wojciech covered the details in last L1calo week*

II. System tests with goal of a successful PRR

- At CERN starting February in Lab 104, high speed backplane testing
- In USA15, full rack testing, mid-end of February
- *We were asked to provide details about time scales and resources needed*

III. Post PRR focus on system integration and commissioning

- Continue tests in Lab 104, focusing on logic and algorithms

I. Initial testing

I. Initial testing

Initial board checkout to be done @ MSU

- Board inspection and final assembly and installation of components
- Grounding and power verification
- Clock testing and characterization
- FPGA programming via JTAG/CF

I. Initial testing

Interface tests to be done @ MSU

- Test data interfaces standalone in loopback
 - CTP outputs, merger cable I/O, SFP optical output, L1topo optical output
- Using the MSU rig (later in parallel with test @ CERN)
- Find parameters to successfully receive 160 Mbps backplane input from single JEM in MSU test rig
 - Special test firmware versions for BF and Topo FPGA, with components from target FW (Wojtek, Pawel)
 - Special FW for JEM for sending direct test patterns at the output to test data integrity (Pawel)
- Embed Chipscope cores for control and monitoring to minimizing SW support
 - At the same time CMX/JEM software is being adapted, possibly use already in interface tests (Duc)

I. Initial testing

Close to target FW for Board Support FPGA (Yuri)

- Control of the AVAGO TXRXs
- LVDS buffer control
- TTC control

Timescale

- Initial board checkout will start end of December/beginning of January
- Pawel and Wojciech perform interface tests @MSU beginning of January, planned for two weeks
- Shipping of initially one CMX to CERN (for full crate test will have two), continue with tests in parallel at MSU with remaining CMX

II. System tests towards PRR

II. System tests towards PRR

Backplane data transmission tests in Lab 104

- Determine and manage the parameters for test rack in lab 104 before full crate tests in USA15
 - Use and continue to develop special CMX and JEM FW that was used in the initial test phase (Pawel, Wojciech)
 - Test data integrity with FW and software elements for the timing procedure (under development) via the backplane line/clock delays (SW: Savanna, Duc, FW: Wojciech)
 - Parity error counters for each input module data
 - Data error flag/counters for each backplane line

II. System tests towards PRR

Backplane data transmission tests in Lab 104, cont.

- Development of software needed prior to the tests (support of new JEP/SumEt capabilities, partially based on software used in initial test phase) and availability of software experts maybe beneficial
- Not testing any algorithms or logic

Further tests in Lab 104, but not needed before USA15 full crate test

- DCS tests
- Full tests of proper electrical/optical operation of all inputs and outputs

II. System tests towards PRR

System tests in USA15 with full crate and two CMX prototypes

- Tests will be done with JEMs only
- Test of full high-speed backplane performance with full crate of at least JEMs for long periods of time
- Redo data integrity test as in CERN test rig
- Power and power quality tests

II. System tests towards PRR

System tests in USA15 with full crate and two CMX prototypes, cont.

- Re-use special FWs used in previous tests
- L1calo standalone partition for one (JEM) crate would be sufficient, no CTP needed
- No other detector systems needed
- Operations experts would be needed to facilitate partition building and running tests concurrently with other sub-systems
 - Would want to have separate partition for CMX test from partition for other L1Calo test or ATLAS subsystems

Timescale

- Earliest start by beginning of February with CERN test rig, continued interface tests in parallel @ MSU
- Full crate test in USA15, middle of February for 1-2 weeks

II. System tests towards PRR

Remarks on full-crate system test

- Tests are planned with JEM (Jet) modules and CMX alone
 - Expertise and support on JEM at hand
 - Looking into having JEM energy sum as well for electrical tests
- Might also require full-crate CPM testing
 - Do not have fully working CPM at hand and cannot test if problems occur which are related to CMX design
 - Would need updated CPM firmware and software, if test with CPM is required for PRR

III. Post PRR testing

III. Post PRR testing and commissioning

Tests @CERN after PRR

- Continue with system tests
- Test algorithms and data content
- Working towards final firmware
- Shift focus to CPM, if it was not fully included before

Installation of CMX production cards for M-runs as soon as...

- PRR successful
- Production of CMX card completed
- Tests of production CMX cards @MSU finished
- Firmware and software ready

Summary

I. Initial testing

- Initial board checkout
- Board interface tests

II. System tests with goal of a successful PRR

- At CERN Lab 104, high speed backplane testing
- In USA15, full rack testing

III. Post PRR focus on system integration and commissioning

- Continue tests in Lab 104, focusing on logic and algorithms

CMX prototypes arrive end of **December**

Initial tests **December/January @MSU**

System tests **beginning of February @CERN Lab 104**

Full rack test **@USA15 mid-February**

Backplane tests for PRR finished by **end of February**

Post PRR test **@MSU and @CERN**

