



Joint L1Calo Meeting


Status of the FEX ATCA Hub Project

Wade Fisher, Dan Edmunds,
Philippe Laurens, Yuri Ermoline

01 October 2015




FEX ATCA Hub






ATCA Hub Current Drawing





ATCA Hub Current Drawing



Optical I/O

ROD
ROD Mezzanine

Hub
FPGA

FEX
Data
1:2
Fanout

Unmanaged
GbE Switch

Design essentially finished, routing in progress

2239 components,
2736 nets,
6594 connections




Design Changes: TTC/Clock

TTC/Clock interface

- Original design included a TTC FMC mezzanine card, swapped out for SFP+
- Current design removes SFP+, replace with spare MiniPod capacity

Anticipating future needs

- Tx/Rx MiniPods previously included to allow for potential for direct Hub/FELIX interface
- Removing SFP+ frees needed floor space
- Allows all optical interfaces to be located in RTM; plan for sharing of MTP connectors with ROD has been established





Design Changes: Backplane Speeds


Backplane link speed options have been reduced

- July 2015: 10.26 Gbps option was eliminated
- Currently supported Hub speeds: 4.8, 6.4, 9.6 Gbps (3.2 gone?)

Zone 2 Fabric Traffic: potentially different link speeds

- FEX → Hub → ROD
- Clock → ROD/FEX
- TTC → ROD/FEX
- Hub1/2 → Hub2/1

Note: FELIX interface may change slightly in Phase-2, but Lorne has confirmed Phase-1 Tx speeds will be supported.






Design Changes: FPGA Choice

Serious study of pro/con for migration from Virtex-7 to Virtex-Ultrascale

- Previous FPGA choice: XC7VX550T/690T (80 MGTs)
- Ultrascale options: XCVU125/160 (80 / 104 MGTs)

Driving considerations

- Can design to the XCVU160
 - Pin compatible with XCVU125
 - Option to fully connect MiniPod channels
 - Cost-neutral with XC7VX1125T (smallest V7 with sufficient MGTs)
- XC7VX550 → XCVU125: 3x in effective logic
 - Ensure option to emulate ROD-like functionality
 - Opens many doors at Phase-2
- Simplifies Hub routing
 - Ultrascale MGT quads have 2 QPLLs; V7 has 1 QPLL, 1 CPLL
- Long-term support more favorable






Design Changes: IPMC

Not so much a design change as change in understanding

- We require that the IPMC provide geographical information
- Important: shelf number

This IPMC functionality was previously in question

- This functionality would otherwise have to be established ad hoc
- Stony Brook LAr team has established IPMC-Shelf manager communications
 - Blade power and hot-swap functions appear to be capable
 - Currently no support for mezzanine communication / power management
 - We weren't counting on this in our ROD/Hub design





Hub Firmware

- ❖ HUB FW working document:
 - Interfaces to the HUB FPGA
 - FEX/ROD data
 - GBT interface
 - IPbus interface
 - Others (e.g. – MiniPOD)
- ❖ Start with the IPbus interface
 - CACTUS FW design examples
 - use as starting point
 - Use vc709 demo board
 - adapting kc705 example
 - Not exactly HUB HW
 - no PHY chip and copper Eth
 - Useful exercise (still not finished)
 - ISE14.7 and Vivado for V7
 - Need more RAM to run
 - VM, licences, board programming...

ATLAS

EDMS Number:
EDMS Id:

1 **ATLAS Level-1 Calorimeter Trigger**

2 **FEX Hub Firmware**

3

4 **Working document**

5

6 Document Version: Draft 0.0

7 Document Date: xx May 2015

8 Prepared by: D. Edmunds, Y. Ermoline, W. Fisher, P. Laurens,
9 Michigan State University, East Lansing, MI, USA

10

11

12 **Document Change Record**

Version	Issue	Date	Comment
0	0	06 April 2015	Initial document layout
0	1	xx May 2015	More about Q&A

13

FEX Hub Firmware Working document page 1



Hub Schedule

- ❖ Layout/design essentially complete at this time
 - Routing in progress
 - Currently aiming at Ultrascale chip implementation
 - Xilinx delivery quote at 10 weeks puts assembly date in mid-December / early January
 - Represents a ~1 month delay on previous schedule

- ❖ Current plan
 - Fabricate blank board for electrical tests (2015)
 - Fab / Assemble test board without FPGA (1/2016)
 - Validate fab process / stack-up
 - Proceed to prototype construction (2/2016)
 - March 2016 commissioning date



Summary

- ❖ The ATCA FEX Hub project is coming along well
 - Several worries have been resolved, a few remain
 - Backplane link speed remains to be demonstrated
 - Move to Ultrascale introduces a delay, but not critical

- ❖ Firmware effort progressing in parallel
 - Nominal expectation that Ultrascale/V7 transition not disruptive
 - Indications so far are promising

- ❖ We're continuing forward on prototype design, with the goal of prototypes in Q1 2016.